

*The reliability and maintainability of the ITER Tokamak Cooling Water System (TCWS) conceptual design were reviewed. The reliability of the TCWS cooling loops was suspect because all elements are required to work in order for the system to support plasma operation. Configuration options for improving the reliability and maintainability of the TCWS cooling loops and chemical and volume control system (CVCS) were proposed.*